



NOTES:

1. CONTRACTOR SHALL STRIKE CONTROL JOINTS EVERY 5'-0" AND PLACE EXPANSION JOINTS EVERY 20'-0".
2. CONTRACTOR TO INSTALL 1/2" PREFORMED EXPANSION JOINT MATERIAL AT ALL EXPANSION JOINTS AND WHERE SIDEWALK ABUTS CONCRETE CURB, FOUNDATIONS, APRONS, OR OTHER CONCRETE STRUCTURES.
3. USE APPROPRIATELY SIZED BACKER ROD AND SELF-LEVELING CONCRETE SEALANT, COLOR: GRAY, OVER ALL SIDEWALK EXPANSION JOINTS.
4. WHERE SIDEWALKS ABUT CURB WITH NO GRASS STRIP, CLUSTER MAILBOXES SHALL BE CONSIDERED IN GRASS AREA BEHIND SIDEWALKS.

CONCRETE SIDEWALK AROUND OBSTRUCTION

NTS



The Town of Mount Airy, Maryland

APPROVED

[Handwritten Signature]

CONCRETE SIDEWALK
AROUND OBSTRUCTION

By:
KMM

Date
11/30/18

Standard Detail No.

R-19